
JAMISON

INSTALLATION INSTRUCTIONS FOR MARK IV HEAVY DUTY VERTICAL SLIDING MANUAL SPLIT DOOR WITH CHAINFALL OPERATOR

AFTER INSTALLING DOOR FORWARD TO MAINTENANCE DEPARTMENT OR OWNER



JAMISON DOOR COMPANY

P.O. BOX 70 HAGERSTOWN, MARYLAND 21741 USA (1-800-532-3667) INTERNET: <u>http://www.jamisondoor.com</u> E-MAIL: <u>sales@jamisondoor.com</u>

CONTENTS

GENERAL INFORMATION	3
CASING INSTALLATION	4
CASING INSTALLATION (FREEZER WITH HEAT IN FRAME OPTION)	7
PLACING DOOR INTO TRACK	8
RIGGING DETAILS FOR COUNTERWEIGHT	9
COUNTERWEIGHT BOX ASSEMBLY	11
DOOR AND GASKET ADJUSTMENTS	12
PULL ROPE AND "FROSTOP" HOOK-UP	14
LUBRICATION	15

GENERAL INFORMATION:

A. CONTENTS OF CRATES AND CARTON

- FRAME COMPONENT PARTS AND ASSEMBLIES SHIPPED KNOCKED-DOWN. NOTE: IF FRAME HAS JAMBS, CASING AND JAMBS ARE SHIPPED IN SEPARATE CRATE.
- 2. ONE CRATE CONTAINING DOOR LEAVES WITH ALL COMPONENTS PARTS AND ASSEMBLIES ATTACHED.
- ONE CARTON CONTAINING:
 a. PACKING LIST ITEMS
 b. INSTALLATION INSTRUCTIONS

B. INSPECT FOR DAMAGE AND SHORTAGE IMMEDIATELY

- 1. NOTE ON ALL COPIES OF DELIVERY RECEIPT ANY APPARENT DAMAGES AND SHORTAGES.
- OPEN ALL SHIPPING CONTAINERS AND INSPECT FOR CONCEALED DAMAGE AND SHORTAGES. CAREFULLY REPACK TO PREVENT DAMAGE AND PILFERAGE.
- 3. REPORT **WITHIN 15 DAYS** IN WRITING TO TRANSPORTATION COMPANY, WITH A COPY TO JAMISON DOOR, ANY CONCEALED DAMAGE AND SHORTAGES. AFTER 15 DAYS, LAWS PERMIT THE TRANSPORTATION COMPANY TO REJECT ALL CLAIMS.

C. HANDLE ALL PARTS CAREFULLY

1. CERTAIN PARTS SUCH AS GASKET, ETC. ARE VULNERABLE.

D. READ ALL INSTRUCTIONS BEFORE PROCEEDING WITH INSTALLATION

- 1. INSTRUCTIONS INCLUDE BASIC DRAWINGS FOR ALL DOORS TYPES.
- 2. USE DRAWINGS APPLICABLE TO YOUR DOOR.
- 3. REFER TO JOB DRAWINGS FOR SPECIAL FEATURES.


E. PLAN AHEAD

- 1. CHOOSE INSTALLERS WHO ARE MILLWRIGHTS OR HAVE EQUAL QUALIFICATIONS.
- 2. HAVE ALL TOOLS AND MATERIALS FOR INSTALLATION READILY AVAILABLE.

NOTE: EUCKS FOR FRAME MUST BE PLUMB, TRUE AND SQUARE. FLOOR THROUGH DOOR OPENING MUST BE LEVEL FULL WIDTH TO PROVIDE PROPER DOOR OPERATION AND GASKET SEAL.

STEPS:

- APPLY CAULKING COMPOUND TO BACK OF CASING MEMBERS.
- 2. BLOCK SIDE CASINGS WITH VERTICAL ANGLES ATTACHED AND HEAD CASING IN PLACE. MAKE SURE VERTICAL ANGLES ARE PLUMB, TRUE AND PARALLEL AND SPREAD AS SHOWN IN <u>DETAIL "A"</u>. USE ROW OF HOLES NEAR TOE OF ANGLE AS TEMPLATE AND DRILL CLEARANCE HOLES THRU CASING AND PILOT HOLES INTO BUCK FOR 3/8" X 4-1/2" LG. LAG BOLTS. <u>NOTE:</u> DO NOT DRILL HOLES IN HEAD CASING AT THIS TIME. INSTALL LAG BOLTS INTO BUCKS, SHIM CASING IF NECESSARY TO MAINTAIN A FLAT, PLUMB AND TWIST FREE CASING.
- 3. ATTACH HEAD CASING AND BOTTOM OF SIDE CASINGS TO BUCKS USING FLAT HEAD WOOD SCREWS WITH FINISHING WASHERS UNDER HEADS, SHIM CASING IF NECESSARY TO MAINTAIN A FLAT, PLUMB AND TWIST FREE CASING.




HEAD CASING VAPOR SEAL 3/8" x 4 ½" LAG SCREWS WITH VAPOR FLAT WASHERS SEAL WIDTH-IN-CLEAR OR 3/8" THRU-BOLTS WITH -SIDE CASING FLAT WASHERS WIDTH IN CLEAR PLUS 10-1/2" (INSIDE TO INSIDE OF ANGLE LEGS) DETAIL "A" VERTICAL ANGLE

1


117700000A 3/11 330000

PLUMB LINE




INSTALL HORIZONTAL SPREADER ANGLE WITH IDLER SUPPORT BRACKET ATTACHED BY BOLTING TO SHEAVE BRACKETS. INSTALL FILLER BLOCK AT FASTENING LOCATIONS BETWEEN BUCK AND SPREADER ANGLE AND IDLER SUPPORT BRACKET. SELECT PROPER THICKNESS BLOCKS TO KEEP FROM PULLING SPREADER ANGLE OUT OF ALIGNMENT. MAKE SURE VERTICAL ANGLES ARE PLUMB. DRILL CLEARANCE HOLES THRU FILLER BLOCKS AND PILOT HOLES INTO BUCKS, INSTALL WALL BOLTS

UPPER SPREADER ANGLE ATTACHMENT




SECURING VERTICAL ANGLES TO BUCKS




- 1. ATTACH HEATED SILL TO CASING WITH FASTENINGS PROVIDED. SILL ASSEMBLY MUST BE LEVEL AND TRUE FROM CASING TO CASING.
- 2. PLUG ELECTRICAL CONNECTOR TOGETHER AT FOUR CORNERS OF FRAME AS SHOWN.
- INSTALL END COVERPLATES, CAULK AND SEAL TO EXCLUDE MOISTURE.
 BRACE HEATED SILL SECURELY AND GROUT IN FINISHED CONCRETE FLOOR AROUND SILL.

CASING ERECTION (SPECIAL FREEZER)


- 1. TEMPORARILY REMOVE UPPER SECTION OF TRACK FROM TRACK BRACKETS.
- 2. LUBRICATE ROLLER SHAFTS AND INSERT ROLLERS INTO BRACKETS ON BOTTOM LEAF.
- 3. LIFT BOTTOM LEAF TO TOP OF VERTICAL TRACK, LOWER LEAF CAREFULLY TO FLOOR. INSTALL UPPER LEAF FOLLOWING SAME PROCEDURE LOWERING TO TOP OF LOWER LEAF.
- 4. ATTACH HINGE TO UPPER LEAF USING FACTORY DRILLED HOLES.
- 5. RE-INSTALL UPPER SECTION OF TRACK, ALIGNING WITH LOWER SECTION.
- 6. FREEZER DODR DNLY SEE SHEET #9 FDR *FROSTOP* HOOK-UP.







DETAIL "A"

PLACING DOOR IN TRACK





RIGGING DETAILS FOR L.H. COUNTERWEIGHT - R.H. COUNTERWEIGHT OPPOSITE




COUNTERWEIGHT BOX ASSEMBLY


ADJUST GASKET

MOVE DOOR TO OPEN POSITION. LOOSEN GASKET ATTACHMENT SCREWS, I PULL OUT GASKET AS REQUIRED TO OBTAIN A GOOD GASKET SEAL (APPROX. 1/8" COMPRESSION). DO NOT OVER COMPRESS GASKET. RE-TIGHTEN ATTACHMENT SCREWS. CHECK FOR PROPER SEAL.

- 1




1 - SEALING GASKET ADJUSTMENT




2 - TRACK ADJUSTMENT

- 1. DPERATE DODR MANUALLY TO CHECK FOR ANY BINDING OR ALIGNMENT PROBLEMS.
- 2. ADJUST DODR FOR PROPER GASKET SEAL. LODSEN TRACK FASTENINGS AND MOVE TRACK IN OR DUT AS REQUIRED TO ACHIEVE A GOOD GASKET SEAL. TIGHTEN ALL TRACK. FASTENINGS. ADJUST FRAME GASKET IF REQUIRED.
- 3. ADJUST CABLE TERMINAL ENDS IF NECESSARY TO ACHIEVE A GASKET SEAL ACROSS SILL. SEE PAGE #6.



DOOR AND GASKET ADJUSTMENTS



LUBRICATION INSTRUCTIONS

LUBRICATE AT 3 MONTH INTERVALS

GREASE - TO BE GOOD GRADE OF LITHIUM BASE GREASE.

OIL ---- TO BE GOOD GRADE OF S.A.E. 30 NON-DETERGENT MOTOR OIL.

1) CABLE SHEAVES BEARINGS - GREASE

2) SPROCKET BEARINGS - OIL

3 CHAIN LOCK - GREASE

- 4) ROLLER CHAIN OIL
- 5 ROLLERS OIL
- 6 LIFTING CABLES APPLY WIRE ROPE LUBRICANT

(8) HINGE KNUCKLES - OIL